


RMK-FS AND ASSOCIATED PARTS

STANDARD RUBBER MOLDED

IN-LINE SERIES

Note: Available with grippers, must specify.

Material: Special Neoprene, Molded
 Contacts: Copper Alloy, Hard Gold Plated per ASTM-B-488
 Voltage Rating: 600 VDC-contact factory for higher voltage requirements
 Pressure Rating, Mated: up to 20,000 psi




WOC CONNECTORS

Note: WOC stands for “without cable.” The connectors are supplied as shown below for installation in the field and/or to non-neoprene jacketed cables. Bonding can be achieved by molding to the connectors shown using polyurethane with appropriate primers. Inexpensive plastic syringes can be used as molds.

Part Names: RMK-FS WOC, RMK-MP WOC

Material: Special Neoprene, Molded
 Contacts: Brass, Hard Gold Plated per ASTM-B-488
 Voltage Rating: 600 VDC-contact factory for higher voltage requirements
 Pressure Rating, Mated: up to 20,000 psi



LOCKING SLEEVES

K-MLS-D (AVAILABLE FOR RMK-MP & RMK-MP WOC)
 K-FLS-D (AVAILABLE FOR RMK-FS, RMK-FS-R/A, RMK-FS WOC)
 K-MLS-S (AVAILABLE FOR RMK-MP, RMK-MP WOC)
 K-FLS-S (AVAILABLE FOR RMK-FS, RMK-FS R/A & RMK-FS WOC)
 K-FLS-X (AVAILABLE FOR RMK-FS)
 (Must specify cable O.D. when ordering K-FLS-X)

DUMMY CONNECTORS

Note: specify number of conductors when ordering

RMK-FSD MATES TO RMK-MP
 RMK-MPD MATES TO RMK-FS & RMK-FS-R/A

Material: Special Neoprene, Molded
 Pressure Rating, Mated:
 RMK-FSD (20,000 PSI)

RMK-MPD-LP (LOW PRESSURE $\leq 4,000$ PSI, NO CONTACT REQUIRED)
 RMK-MPD-HP (4,000-20,000 PSI CONTACT IS REQUIRED)