

VMK-FS AND ASSOCIATED PARTS

REVERSED RUBBER MOLDED


IN-LINE SERIES

Material: Special Neoprene, Molded

Contacts: Copper Alloy, Hard Gold Plated per ASTM-B-488

Voltage Rating: 600 VDC-contact factory for higher voltage requirements

Pressure Rating, Mated: up to 20,000 psi



WOC CONNECTORS

Note: WOC stands for "without cable." The connectors are supplied as shown below for installation in the field and/or to non-neoprene jacketed cables. Bonding can be achieved by molding to the connectors shown using polyurethane with appropriate primers.


Part Names: VMK-FS WOC, VMK-MP WOC

Material: Special Neoprene, Molded

Contacts: Brass, Hard Gold Plated per ASTM-B-488

Voltage Rating: 600 VDC-contact factory for higher voltage requirements

Pressure Rating, Mated: up to 20,000 psi



LOCKING SLEEVES

K-MLS-D (AVAILABLE FOR VMK-MP, VMK-MP WOC)

K-FLS-D (AVAILABLE FOR VMK-FS, VMK-FS-R/A, VMK-FS WOC)

DUMMY CONNECTORS

Notes: Specify number of conductors when ordering

VMK-FSD MATES TO VMK-MP
VMK-MPD MATES TO VMK-FS & VMK-FS R/A

Material: Special Neoprene, Molded

Pressure Rating, Mated:

VMK-FSD-LP (LOW PRESSURE $\leq 4,000$ PSI, NO CONTACT REQUIRED)

VMK-FSD-HP (4,000-20,000 PSI CONTACT IS REQUIRED)

VMK-MPD (20,000 PSI, NO CONTACT REQUIRED)