

VMK-FS AND ASSOCIATED PARTS

MATEABLE BULKHEAD CONNECTORS

BULKHEAD CONNECTORS

(MATES TO VMK-FS & VMK-FS-R/A & VMK FS WOC)

Dummy Connector VMK-FSD


Part Name: **VMK-BCL**

Material: 316 Stainless St.; Internal Insulation: Special Neoprene

Contacts: Copper Alloy, Hard Gold Plated per ASTM-B-488

Pressure Rating, Mated: up to 20,000 psi

VMK-BCL; Special Insulating neoprene is permanently molded to the metal shell. These types of connectors are used where physical abuse would be too great for the non-metallic (glass reinforced epoxy) series. The VMK BCL has a locking sleeve provision and utilizes a facial O-ring seal to the bulkhead.







Part Name: **VSK-BCL**

Material: Glass Reinforced Epoxy

Contacts: Copper Alloy, Hard Gold Plated per ASTM-B-488

Pressure Rating, Mated: up to 20,000 psi

VSK-BCL; One of our oldest connectors in the non-metallic series, with male pin as shown. Connector is one homogeneously molded unit. Available with different thread lengths as indicated. The VSK BCL has a locking sleeve provision and utilizes a facial O-ring seal to the bulkhead.



NOTE: Torque values referenced in this literature assume installation into dry metal threads. Please contact the factory for recommendations.