

Microwave Path Data Sheet

Page 1 of 1

COMSEARCH

19700 Janelia Farm Boulevard, Ashburn, VA, 20147
(703)726-5729 www.comsearch.com

PCN Date: 12/08/2009

Job Number: 091208COMSFB10

New Path

RCN Number: 09120824

Administrative Information

BA12012A WR CA

City/County /Contra Costa
Status / License Basis Engineering Proposal / PRIMARY OPERATION
Call Sign
Licensee Code OMNPTC
Licensee Name T-Mobile License LLC
Radio Service / Station Class CF -- Point-to-Point Microwave, Common Carrier

BA51967A CHE CA

San Ramon/Contra Costa
Engineering Proposal / PRIMARY OPERATION
OMNPTC
T-Mobile License LLC
FXO -- Fixed

Site Information

Latitude (NAD 83)	37 ° 44' 20.0~ N	37 ° 45' 32.1~ N
Longitude (NAD 83)	121 ° 59' 42.5~ W	121 ° 57' 30.7~ W
Ground Elevation (m/ft-AMSL)	561.80 / 1843.2	131.98 / 433.0
Antenna Structure Registration #	1222544	
Path Azimuth (°)	55.424	235.447
Path Length (km / miles)		3.918 / 2.435

Transmit Antenna

87012A
Manufacturer ANDREW CORPORATION
Model VHLP2-18
Gain (dBi) / Beamwidth (°) / Tilt (°) 38.7 / 2.10 / -5.96
Centerline (m / ft - AGL) 11.58 / 38.0

87012A
ANDREW CORPORATION
VHLP2-18
38.7 / 2.10 / 5.93
33.53 / 110.0

Receive Antenna

Same As Transmit

Manufacturer
Model
Gain (dBi) / Beamwidth (°)
Centerline (m / ft - AGL)

Diversity Receive Antenna

Manufacturer
Model
Gain (dBi) / Beamwidth (°)
Centerline (m / ft - AGL)

Radio Information

TEMJ43
ALCATEL-LUCENT
AL0H18004008T110
9518 MXC 8DS1 QPSK
10M0G7W QPSK
192 CH DIG 12400.000
0.001
Nominal Coordinated Maximum
12.0
-40.4
50.7

TEMJ43
ALCATEL-LUCENT
AL0H18004008T110
9518 MXC 8DS1 QPSK
10M0G7W QPSK
192 CH DIG 12400.000
0.001
Nominal Coordinated Maximum
12.0
-40.4
50.7

Power (dBm)
Received Level (dBm)
EIRP (dBm)
Fixed Loss: Tx / Common (dB) 0.0 / 0.0
Free Space Loss (dB) 129.8

0.0 / 0.0

Transmit Frequencies (MHz) 17875.0000V(6)

19435.0000V(6)