

Micronet Communications, Inc.
 720 F Avenue, Suite 100
 Plano, Texas 75074
 972-422-7200

File: M0535503 1

Updated PCN Date: February 11, 2011

Company: NEXTWEB INC

Company Code	#14370	#14370
FRN	0004515185	0004515185
Site Name, State	PLR, CA	Sunol, CA
Call Sign/County	WQEU573/Alameda	WQEU574/Alameda
City	Pleasanton	SUNOL
Latitude N (NAD83)	37 39 34.00	37 37 12.00
Longitude W (NAD83)	121 55 59.50	121 55 17.00
Azimuth (degrees)	166.61	346.62
Distance (miles/km)	2.80/4.50	2.80/4.50
Space Loss (dB)	130.968	
Elevation AMSL (ft/m)	1487.9/453.50	2183.1/665.40
ASR	1015996	

Transmit-Receive Ant Type	VHLP2-180	VHLP2-180
FCC Designation		
Antenna Manufacturer	ANDREW	ANDREW
Gain/Beamwidth (dbi/deg)	38.7/1.8	38.7/1.8
Antenna Height AGL (ft/m)	40.00/12.19	20.00/6.10
Tilt (degrees)	2.603	-2.634

Diversity Receive Ant Type
 FCC Designation
 Antenna Manufacturer
 Gain/Beamwidth (dbi/deg)
 Antenna Height AGL (ft/m)

Equipment Manufacturer	CERAGON NETWORKS	CERAGON NETWORKS
Manufacturer's Type	FIBEAIR 1528PI-18	FIBEAIR 1528PI-18
FCC Identifier		
Emission/Stability %	28M0D7W/0.001	28M0D7W/0.001
ATPC/Trigger Level (dbm)	NO/	NO/
Transmitter Power (dbm/Watts)	20.00/0.1000	20.00/0.1000
Fixed Losses Cm,Tx,Rx (db)	0.0,0.0,0.0	0.0,0.0,0.0

Receive Level (dbm)	-33.57	-33.57
EIRP (dbm/Watts)	58.70/741.31	58.70/741.31
Traffic (kbps/vc)	116000.0/1	116000.0/1
Modulation/Lvl	QAM/32	QAM/32
Frequencies Transmitted (MHz)	19520.0V	17960.0V