

Comware V7 FTP NETCONF XML API Configuration Reference

Contents

- FTP]
- FTP/Server]
- XML structure]
- Table description]
- Columns]

FTP

FTP/Server

This table contains information about global FTP Server functions.

XML structure

```
<FTP>
  <Server>
    <State></State>
    <Ipv4DSCP></Ipv4DSCP>
    <Ipv6DSCP></Ipv6DSCP>
    <Ipv4ACLNum></Ipv4ACLNum>
    <Ipv6ACLNum></Ipv6ACLNum>
    <Timeout></Timeout>
    <SslServerPolicy></SslServerPolicy>
  </Server>
</FTP>
```

Table description

Item	Description
Feature name	FTP
Table name	Server
Table type	Single-instance table
Row name	None
Restrictions	This table supports only global FTP Server functions.
Support for row creation and deletion	No

Columns

Column name	Column description	Column type	Data type and restrictions
State	Global FTP Server feature	N/A	EnableState: • enable Enable FTP Server • disable Disable FTP Server(default)

Column name	Column description	Column type	Data type and restrictions
Ipv4DSCP	Set the IPv4 Differentiated Services Codepoint (DSCP) value	N/A	Unsigned integer. Value range: 0 to 63. Default value:0
Ipv6DSCP	Set the IPv6 Differentiated Services Codepoint (DSCP) value	N/A	Unsigned integer. Value range: 0 to 63. Default value:0.
Ipv4ACLNum	Specify an IPv4 ACL used to control the FTP clients' access	N/A	Unsigned integer. Value range: 2000 to 3999.
Ipv6ACLNum	Specify an IPv6 ACL used to control the FTP clients' access	N/A	Unsigned integer. Value range: 2000 to 3999.
Timeout	Specify FTP timeout value	N/A	Unsigned integer. Value range: 1 to 35791. Default value: 30.
SslServerPolicy	Specify an SSL server policy for the FTP server	N/A	String. Length: 1 to 31 characters.