

Comware V7 Fundamentals NETCONF XML API Configuration Reference

Copyright © 2013 Hangzhou H3C Technologies Co., Ltd. All rights reserved.
No part of this manual may be reproduced or transmitted in any form or by any means
without prior written consent of Hangzhou H3C Technologies Co., Ltd.
The information in this document is subject to change without notice.



Contents

- Fundamentals..... 1
 - Fundamentals/WebUI..... 1
 - XML structure..... 1
 - Table description..... 1
 - Columns..... 1

Fundamentals

Fundamentals/WebUI

This table contains Web service information.

XML structure

```
<Fundamentals>
  <WebUI>
    <SessionAgingTime></SessionAgingTime>
    <HTTP>
      <State></State>
      <Port></Port>
      <AcINumber></AcINumber>
    </HTTP>
    <HTTPS>
      <State></State>
      <Port></Port>
      <AcINumber></AcINumber>
    </HTTPS>
  </WebUI>
</Fundamentals>
```

Table description

Item	Description
Feature name	Fundamentals
Table name	WebUI
Table type	Single-instance table
Row name	N/A
Restrictions	None
Support for row creation and deletion	No

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
SessionAgingTime	Web user connection timeout (minutes)	N/A	Unsigned integer. Value range: 1 to 999.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
HTTP	HTTP configuration information.	Data structure	Members include: • State • Port • AclNumber	N/A
State	HTTP status.	N/A	Enumeration: • enable • disable	N/A
Port	HTTP port number.	N/A	Unassigned integer. Value range: 1 to 65535.	N/A
AclNumber	HTTP ACL number in use.	N/A	Unassigned integer. Value range: 2000 to 2999.	Applicable to only basic ACLs.
HTTPS	HTTPS configuration information.	Data structure	Members include: • State • Port • AclNumber	N/A
State	HTTPS status.	N/A	Enumeration: • enable • disable	N/A
Port	HTTPS port number.	N/A	Unassigned integer. Value range: 1 to 65535.	N/A
AclNumber	HTTPS ACL number in use.	N/A	Unassigned integer. Value range: 2000 to 2999.	Applicable to only basic ACLs.