

# Comware V7 OBJP NETCONF XML API Action Reference

---

# Contents

- OBJP..... 1
  - OBJP/ClearZoneStatistic ..... 1
    - XML structure ..... 1
    - Table description ..... 1
    - Columns ..... 1
  - OBJP/ClearAllStatistic ..... 2
    - XML structure ..... 2
    - Table description ..... 2
    - Columns ..... 2

# OBJP

## OBJP/ClearZoneStatistic

This table contains the operation information for an security zone pair object policy.

### XML structure

```
<OBJP>
  <ClearZoneStatistic>
    <Zonepair>
      <SrcZone></SrcZone>
      <DestZone></DestZone>
      <ClearType></ClearType>
      <Clear></Clear>
    </Zonepair>
  </ClearZoneStatistic>
</OBJP>
```

### Table description

| Item         | Description          |
|--------------|----------------------|
| Feature name | OBJP                 |
| Table name   | ClearZoneStatistic   |
| Table type   | Multi-instance table |
| Row name     | Zonepair             |
| Restrictions | None                 |

### Columns

| Column name | Column description                | Column type | Data type and restrictions                                                                                 | Remarks                                                                                    |
|-------------|-----------------------------------|-------------|------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|
| SrcZone     | Name of the source zone.          | Index       | String, case-insensitive.<br>Length: 1 to 31 characters.                                                   | N/A                                                                                        |
| DestZone    | Name of the destination zone.     | Index       | String, case-insensitive.<br>Length: 1 to 31 characters.                                                   | N/A                                                                                        |
| ClearType   | Type of statistics to be cleared. | N/A         | Enumeration: <ul style="list-style-type: none"><li>1—IPv4 statistics.</li><li>2—IPv6 statistics.</li></ul> | Optional.<br>If you do not specify this column, both IPv4 and IPv6 statistics are cleared. |

| Column name | Column description                                  | Column type | Data type and restrictions | Remarks   |
|-------------|-----------------------------------------------------|-------------|----------------------------|-----------|
| Clear       | Clears security zone pair object policy statistics. | N/A         | This column must be empty. | Required. |

## OBJP/ClearAllStatistic

This table contains the operation information for all security zone pair object policies.

### XML structure

```
<OBJP>
  <ClearAllStatistic>
    <ClearType></ClearType>
    <Clear></Clear>
  </ClearAllStatistic>
</OBJP>
```

### Table description

| Item         | Description           |
|--------------|-----------------------|
| Feature name | OBJP                  |
| Table name   | ClearAllStatistic     |
| Table type   | Single-instance table |
| Row name     | N/A                   |
| Restrictions | None                  |

### Columns

| Column name | Column description                                  | Column type | Data type and restrictions                                                                                    | Remarks                                                                                    |
|-------------|-----------------------------------------------------|-------------|---------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|
| ClearType   | Type of statistics to be cleared.                   | N/A         | Enumeration: <ul style="list-style-type: none"> <li>1—IPv4 statistics.</li> <li>2—IPv6 statistics.</li> </ul> | Optional.<br>If you do not specify this column, both IPv4 and IPv6 statistics are cleared. |
| Clear       | Clears security zone pair object policy statistics. | N/A         | This column must be empty.                                                                                    | Required.                                                                                  |