

Comware V7 PKEY NETCONF XML API Data Reference

Contents

PKEY.....	1
PKEY/LocalKeys	1
XML structure.....	1
Table description	1
Columns.....	1
PKEY/DefaultLocalKeys	2
XML structure.....	2
Table description	2
Columns.....	3
PKEY/PeerKeys.....	3
XML structure.....	3
Table description	4
Columns.....	4
PKEY/GetSSHPublicKeys	4
XML structure.....	4
Table description	5
Columns.....	5
PKEY/SSHFormats	5
XML structure.....	5
Table description	6
Columns.....	6
PKEY/PKEYCapabilities.....	6
XML structure.....	6
Table description	7
Columns.....	7

PKEY

PKEY/LocalKeys

This table is used to get local public keys.

XML structure

```
<PKEY>
  <LocalKeys>
    <Key>
      <AlgID></AlgID>
      <KeyName></KeyName>
      <Length></Length>
      <CreateTime></CreateTime>
      <Value></Value>
    </Key>
  </LocalKeys>
</PKEY>
```

Table description

Item	Description
Feature name	PKEY
Table name	LocalKeys
Table type	Multi-instance table
Row name	Key
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
AlgID	Identity of algorithm	Index	Unsigned integer. Value range: 1 to 2 ³² -1.	See table PKEYCapabilities for supported algorithm.
KeyName	Name of local asymmetric key	Index	String. Length: 1 to 64 characters.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
			Case insensitive	
Length	Length of local asymmetric key	N/A	Unsigned integer.	N/A
CreatedTime	When is the key created	N/A	DateTime. Format:HH:MM:SS YYYY/MM/DDT	N/A
Value	The value of public key	N/A	PKCS#1 formatted hex string.	N/A

PKEY/DefaultLocalKeys

This table is used to get default local public keys.

XML structure

```

<PKEY>
  <LocalKeys>
    <Key>
      <AlgID></AlgID>
      <Usage></Usage>
      <Length></Length>
      <CreatedTime></CreatedTime>
      <Value></Value>
    </Key>
  </LocalKeys>
</PKEY>

```

Table description

Item	Description
Feature name	PKEY
Table name	DefaultLocalKeys
Table type	Multi-instance table
Row name	Key
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
AlgID	Identity of algorithm	Index	Unsigned integer. Value range: 1 to 2 ³² -1.	See table PKEYCapabilities for supported algorithm.
Usage	Key Usage	Index	Enumeration: • 1—HostKey. • 2—ServerKey	ServerKey is only meaningful for RSA, while HostKey is meaningful for all supported algorithms.
Length	Length of local asymmetric key	N/A	Unsigned integer.	N/A
CreatedTime	When is the key created	N/A	DateTime. Format:HH:MM:SS YYYY/MM/DDT	N/A
Value	The value of key	N/A	PKCS#1 formatted hex string.	N/A

PKEY/PeerKeys

This table is used to get peer public keys.

XML structure

```
<PKEY>
  <PeerKeys>
    <Key>
      <PeerKeyName></PeerKeyName>
      <AlgID></AlgID>
      <Length></Length>
      <Value></Value>
    </Key>
  </PeerKeys>
</PKEY>
```

Table description

Item	Description
Feature name	PKEY
Table name	PeerKeys
Table type	Multi-instance table
Row name	Key
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PeerKeyName	Name of peer public key	Index	String. Length: 1 to 31 characters. Case sensitive	N/A
AlgID	Identity of algorithm	N/A	Unsigned integer. Value range: 1 to 2 ³² -1.	See table PKEYCapabilities for supported algorithm.
Length	Length of asymmetric key	N/A	Unsigned integer.	N/A
Value	The value of key	N/A	PKCS#1 formatted hex string.	N/A

PKEY/GetSSHPublicKeys

This table is used to export local public key to SSH formatted data.

XML structure

```
<PKEY>
  <GetSSHPublicKeys>
    <Key>
      <AlgID></AlgID>
      <KeyName></KeyName>
      <FormatID></FormatID>
      <Value></Value>
    </Key>
  </GetSSHPublicKeys>
</PKEY>
```

Table description

Item	Description
Feature name	PKEY
Table name	GetSSHPublicKeys
Table type	Multi -instance table
Row name	Key
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
AlgID	Identity of algorithm	Index	Unsigned integer. Value range: 1 to 2 ³² -1.	See table PKEYCapabilities for supported algorithm.
KeyName	Name of local asymmetric key	Index	String. Length: 0 to 64 characters. Case insensitive.	A key name with 0 characters belongs to a default key.
FormatID	Identity of SSH format	Index	Unsigned integer. Value range: 1 to 2 ³² -1.	See table SSHFormats for supported algorithm.
Value	Information of SSH format key	N/A	String. Length: 1 to 2048 characters.	N/A

PKEY/SSHFormats

This table described supported SSH format

XML structure

```
<PKEY>
  <SSHFormats>
    <SSHFormat>
      <FormatID></FormatID>
      <FormatName></FormatName>
    </SSHFormat>
  </SSHFormats>
</PKEY>
```

Table description

Item	Description
Feature name	PKEY
Table name	SSHFormats
Table type	Multi -instance table
Row name	SSHFormat
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
FormatID	Identity of SSH format	Index	Unsigned integer.	N/A
FormatName	Name of supported SSH format	N/A	String. Length: 1 to 255 characters Case insensitive	N/A

PKEY/PKEYCapabilities

This table contains supported PKEY algorithm information

XML structure

```
<PKEY>
  <PKEYCapabilities>
    <PKEYCapability>
      <AlgID></AlgID>
      <AlgName></AlgName>
      <MinLength></MinLength>
      <MaxLength></MaxLength>
      <DefaultLength></DefaultLength>
      <ExportFormatIDList>
        <IDItem></IDItem>
      </ExportFormatIDList>
    </PKEYCapability>
  </PKEYCapabilities>
</PKEY>
```


Table description

Item	Description
Feature name	PKEY
Table name	PKEYCapabilities
Table type	Multi-instance table
Row name	PKEYCapability
Restrictions	None.

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
AlgID	Identity of algorithm	Index	Unsigned integer. Value range: 1 to $2^{32}-1$.	N/A
AlgName	Name of algorithm	N/A	String. Length: 1 to 255 characters. Case insensitive.	The name of supported algorithm
MinLength	Minimal length of supported algorithm	N/A	Unsigned integer.	N/A
MaxLength	Maximal length of supported algorithm	N/A	Unsigned integer.	N/A
DefaultLength	Default length of supported algorithm	N/A	Unsigned integer.	N/A
ExportFormatList	Supported export SSH format list	Data structure	Members include: • IDItem.	N/A
IDItem	Identity of SSH format	N/A	Unsigned integer. Value range: 1 to $2^{32}-1$	Contains up to 3 IDItem in ExportFormatList.