

Comware V7 Session NETCONF XML API Data Reference

Contents

Session	1
Session/Ipv4Persistent	1
XML structure	1
Table description	1
Columns	1
Session/Ipv6Persistent	2
XML structures	2
Table description	2
Columns	2
Session/L4StateAgingTime	2
XML structure	2
Table description	3
Columns	3
Session/AppAgingTime	4
XML structure	4
Table description	5
Columns	5
Session/LogThreshold	6
XML structure	6
Table description	6
Columns	7
Session/Ipv4LogOnInterfaces	7
XML structure	7
Table description	8
Columns	8
Session/Ipv6LogOnInterfaces	8
XML structure	8
Table description	9
Columns	9
Session/HotBackup	10
XML structure	10
Table description	10
Columns	10
Session/SessionStatistics	10
XML structure	10
Table description	12
Columns	12
Session/ConnectionLimit/Ipv4Policies	15
XML structure	15
Table description	16
Columns	16
Session/ConnectionLimit/Ipv6Policies	16
XML structure	16
Table description	16
Columns	17
Session/ConnectionLimit/Ipv4LimitRules	17
XML structure	17
Table description	17
Columns	18

Session/ConnectionLimit/Ipv6LimitRules	19
XML structure	19
Table description	19
Columns	20
Session/ConnectionLimit/Ipv4PolicyAppliedGlobally	21
XML structure	21
Table description	21
Columns	22
Session/ConnectionLimit/Ipv6PolicyAppliedGlobally	22
XML structure	22
Table description	22
Columns	22
Session/ConnectionLimit/Ipv4PolicyOnInterfaces	23
XML structure	23
Table description	23
Columns	23
Session/ConnectionLimit/Ipv6PolicyOnInterfaces	24
XML structure	24
Table description	24
Columns	24
Session/ConnectionLimit/GlobalStatistics	25
XML structure	25
Table description	25
Columns	25
Session/ConnectionLimit/InterfaceStatistics	26
XML structure	26
Table description	26
Columns	27

Session

Session/Ipv4Persistent

This table contains IPv4 persistent sessions' information.

XML structure

```
<Session>
  <Ipv4Persistent>
    <ACLNumber></ACLNumber>
    <AgingTime></AgingTime>
  </Ipv4Persistent>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv4Persistent
Table type	Single-instance table
Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
ACLNumber	IPv4 ACL number	N/A	Unsigned integer. Value range: 2000 to 3999.	N/A
AgingTime	Aging time for IPv4 persistent sessions (hours).	N/A	Unsigned integer. Value range: 0 to 360. Default: 24.	0 indicates never ageing. This column can only be configured when <i>ACLNumber</i> is also configured.

Session/Ipv6Persistent

This table contains IPv6 persistent sessions' information.

XML structures

```
<Session>
  <Ipv6Persistent>
    <ACLNumber></ACLNumber>
    <AgingTime></AgingTime>
  </Ipv6Persistent>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv6Persistent
Table type	Single-instance table
Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
ACLNumber	IPv6 ACL number	N/A	Unsigned integer. Value range: 2000 to 3999.	N/A
AgingTime	Aging time for IPv6 persistent sessions (hours).	N/A	Unsigned integer. Value range: 0 to 360. Default: 24.	0 indicates never agging. This column can only be configured when <i>ACLNumber</i> is also configured.

Session/L4StateAgingTime

This table contains the aging time for the sessions in transport layer protocol states.

XML structure

```
<Session>
```

```

<L4StateAgingTime>
  <AgingTime>
    <StateID></StateID>
    <StateName></StateName>
    <TimeValue></TimeValue>
  </AgingTime>
</L4StateAgingTime>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	L4StateAgingTime
Table type	Multi-instance table
Row name	AgingTime
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
StateID	Transport layer protocol state ID.	Index	Unsigned integer. Value range: 0 to 18. 0—SYN-SENT and SYN-RCV (TCP) 1—ESTABLISHED (TCP). 2—FIN-WAIT (TCP). 3—UDP-OPEN. 4—UDP-READY. 5—ICMP -REQUEST. 6—ICMP -REPLY. 7—RAWIP-OPEN. 8—RAWIP-READY. 9—UDPLITE-OPNE. 10—UDPLITE-READY. 11—DCCP-REQUEST. 12—DCCP-EST. 13—DCCP-CLOSEREQ. 14—SCTP-INIT. 15—SCTP-EST. 16—SCTP-SHUTDOWN. 17—ICMPV6-REQUEST.	The aging time can be configured if is the protocol ID is 0 to 8. The aging times for other protocols use the default value.

Column name	Column description	Column type	Data type and restrictions	Remarks
			18—ICMPV6-REPLAY.	
StateName	Transport layer protocol state name.	N/A	String, case-insensitive. Length: 1 to 63 characters.	N/A
			Unsigned integer. Value range: 5 to 100000 seconds. Default aging time for sessions in different protocol states is as follows: 0—SYN-SENT or SYN-RCV (TCP) : 30 1—ESTABLISHED (TCP) : 3600 2—FIN-WAIT (TCP): 30 3—UDP -OPEN : 30 4—UDP -READY : 60 5—ICMP -REQUEST : 60 6—ICMP -REPLY : 30 7—RAWIP-OPEN : 30 8—RAWIP-READY : 60 9—UDPLITE-OPNE : 30 10—UDPLITE-READY : 60 11—DCCP-REQUEST : 30 12—DCCP-EST : 3600 13—DCCP-CLOSEREQ : 30 14—SCTP-INIT : 30 15—SCTP-EST : 3600 16—SCTP-SHUTDOWN:30 17—ICMPV6-REQUEST :60 18—ICMPV6-REPLAY : 30	
TimeValue	Aging time (seconds).	N/A		N/A

Session/AppAgingTime

This table contains the aging time for the sessions of application layer protocols.

XML structure

```

<Session>
  <AppAgingTime>
    <AgingTime>
      <AppID></AppID>
      <AppName></AppName>
      <TimeValue></TimeValue>
    
```

```

    </AgingTime>
  </AppAgingTime>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	AppAgingTime
Table type	Multi-instance table
Row name	AgingTime
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
AppID	Application layer protocol ID.	Index	Unsigned integer. Value range: 0 to 16. • 0—DNS. • 1—FTP. • 2—GTP. • 3—H.225. • 4—H.245. • 5—RAS. • 6—RTSP. • 7—SIP. • 8—TFTP. • 9—IIS. • 10—MGCP. • 11—NBT. • 12—PPTP. • 13—RSH. • 14—SCCP. • 15—SQLNET. • 16—XDMCP.	N/A
AppName	Application layer protocol name.	N/A	String, case-insensitive. Length: 1 to 63 characters.	N/A
TimeValue	Aging time (seconds).	N/A	Unsigned integer. Value range: 5 to 100000 seconds. Default aging time for sessions of application layer protocols is	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
			as follows:	
			• 0—DNS: 60. • 1—FTP: 3600. • 2—GTP: 60. • 3—H.225: 3600. • 4—H.245: 3600. • 5—RAS: 300. • 6—RTSP: 3600. • 7—SIP: 300. • 8—TFTP: 60. • 9—IIS: 3600. • 10—MGCP: 60. • 11—NBT: 3600. • 12—PPTP: 3600. • 13—RSH: 60. • 14—SCCP: 3600. • 15—SQLNET: 600. • 16—XDMCP: 3600.	

Session/LogThreshold

This table contains threshold for session logging.

XML structure

```

<Session>
  <LogThreshold>
    <TimeThreshold></TimeThreshold>
    <FlowThreshold>
      <Type></Type>
      <Threshold></Threshold>
    </FlowThreshold>
  </LogThreshold>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	LogThreshold
Table type	Single-instance table

Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
TimeThreshold	Time-based session logging threshold (minutes).	N/A	Unsigned integer. Value range: 10 to 120.	The value must be integer times of 10.
FlowThreshold	Traffic-based session logging threshold (minutes).	Data structure.	Members include: - Type. - Threshold.	
Type	Type of traffic-based session logging.	N/A	Enumeration: 0—Packet-based threshold for traffic-based logging. 1—Byte-based threshold for traffic-based logging.	If you set both the byte-based and packet-based thresholds, the last configuration takes effect.
Threshold	Threshold for traffic-based logging.	N/A	Unsigned integer. Value range: 1 to 1000.	If type is 0, the unit is mega-packets. If type is 1, the unit is mega-bytes.

Session/Ipv4LogOnInterfaces

This table contains interfaces on which IPv4 session logging is enabled.

XML structure

```

<Session>
  <Ipv4LogOnInterfaces>
    <Interface>
      <IfIndex></IfIndex>
      <Direction></Direction>
      <ACLNumber></ACLNumber>
    </Interface>
  </Ipv4LogOnInterfaces>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	Ipv4LogOnInterfaces
Table type	Multi-instance table
Row name	Interface
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
IfIndex	Interface index.	Index	Unsigned integer.	This column can only be the index of local VA, global VA or 3 layer interface except loopback, NULL, FC, FCB and encrypt interface.
Direction	Direction of the interface where session logging is enabled.	Index	Enumeration: • 0—Inbound. • 1—Outbound.	N/A
ACLNumber	IPv4 ACL number.	N/A	Unsigned integer. Value range: 2000 to 3999.	If an ACL is specified, this configuration enables session logging for sessions that match the permit statements in the ACL. If no ACL is specified, this configuration enables session logging for all IPv4 sessions on the interface. This column can be null.

Session/Ipv6LogOnInterfaces

This table contains interfaces to which IPv6 session logging is enabled.

XML structure

```
<Session>
  <Ipv6LogOnInterfaces>
```

```

<Interface>
  <IfIndex></IfIndex>
  <Direction></Direction>
  <ACLNumber></ACLNumber>
</Interface>
</Ipv6LogOnInterfaces>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	Ipv6LogOnInterfaces
Table type	Multi-instance table
Row name	Interface
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
IfIndex	Interface index.	Index	Unsigned integer.	This column can only be the index of local VA, global VA or 3 layer interface except loopback, NULL, FC, FCB and encrypt interface.
Direction	Direction of the interface where session logging is enabled.	Index	Enumeration: 0—Inbound. 1—Outbound.	N/A
ACLNumber	IPv6 ACL number.	N/A	Unsigned integer. Value range: 2000 to 3999.	If an ACL is specified, this configuration enables session logging for sessions that match the permit statements in the ACL. If no ACL is specified, this configuration enables session logging for all IPv6 sessions on the interface. This column can be null.

Session/HotBackup

This table contains session hot backuping configurations.

XML structure

```
<Session>
  <HotBackup>
    <EnableHotBackup></EnableHotBackup>
  </HotBackup>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	HotBackup
Table type	Single-instance table
Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
EnableHotBackup	Whether enable hot backuping for session tables.	N/A	Boolean: - true - false (default).	N/A

Session/SessionStatistics

This table contains statistics of sessions.

XML structure

```
<Session>
  <SessionStatistics>
    <SessionStatistic>
      <Chassis></Chassis>
      <Slot></Slot>
      <CPUID></CPUID>
    </SessionStatistic>
  </SessionStatistics>
</Session>
```

```

<CurSessionCount></CurSessionCount>
<CurRelationCount></CurRelationCount>
<SessionCount>
  <TCPCount></TCPCount>
  <UDPCount></UDPCount>
  <ICMPCount></ICMPCount>
  <ICMPv6Count></ICMPv6Count>
  <UDPLiteCount></UDPLiteCount>
  <SCTPCount></SCTPCount>
  <DCCPCount></DCCPCount>
  <RawIPCount></RawIPCount>
</SessionCount>
<SessionEstablishedRate>
  <TCPRate></TCPRate>
  <UDPRate></UDPRate>
  <ICMPRate></ICMPRate>
  <ICMPv6Rate></ICMPv6Rate>
  <UDPLiteRate></UDPLiteRate>
  <SCTPRate></SCTPRate>
  <DCCPRate></DCCPRate>
  <RawIPRate></RawIPRate>
</SessionEstablishedRate>
<ReceivedPktsBytes>
  <TCPBytes></TCPBytes>
  <TCPPkts></TCPPkts>
  <UDPBytes></UDPBytes>
  <UDPPkts></UDPPkts>
  <ICMPBytes></ICMPBytes>
  <ICMPPkts></ICMPPkts>
  <ICMPv6Bytes></ICMPv6Bytes>
  <ICMPv6Pkts></ICMPv6Pkts>
  <UDPLiteBytes></UDPLiteBytes>
  <UDPLitePkts></UDPLitePkts>
  <SCTPBytes></SCTPBytes>
  <SCTPPkts></SCTPPkts>
  <DCCPBytes></DCCPBytes>
  <DCCPPkts></DCCPPkts>
  <RawIPBytes></RawIPBytes>
  <RawIPPkts></RawIPPkts>
</ReceivedPktsBytes>
</SessionStatistic>
</SessionStatistics>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	SessionStatistics
Table type	Multi-instance table
Row name	SessionStatistic
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
Chassis	ID of the member where the entity resides	Index	Unsigned integer. Value range: 0 to 65534.	N/A
Slot	Slot ID of the entity	Index	Unsigned integer. Value range: 0 to 65534.	N/A
CPUID	CPU ID	Index	Unsigned integer. Value range: 0 to 7.	N/A
CurSessionCount	Total number of current sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
CurRelationCount	Total number of current relation entries.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
SessionCount	Number of sessions of different protocols.	Data structure.	Members include: • TCPCount. • UDPCount. • ICMPCount. • ICMPv6Count. • UDPLiteCount. • SCTPCount. • DCCPCount. • RawIPCount.	N/A
TCPCount	Number of TCP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
UDPCount	Number of UDP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
ICMPCount	Number of ICMP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
ICMPv6Count	Number of	N/A	Unsigned integer.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
	ICMPv6 sessions.		Value range: 0 to $2^{32} - 1$.	
UDPLiteCount	Number of UDP-Lite sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
SCTPCount	Number of SCTP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
DCCPCount	Number of DCCP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
RawIPCount	Number of Raw IP sessions.	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
SessionEstablishedRate	Session establishment rate, and rates for establishing sessions of different protocols.	Data structure.	Members include: • TCPRate. • UDPRate. • ICMPRate. • ICMPv6Rate. • UDPLiteRate. • SCTPRate. • DCCPRate. • RawIPRate.	N/A
TCPRate	Establishment rate of TCP sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
UDPRate	Establishment rate of UDP sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
ICMPRate	Establishment rate of ICMP sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
ICMPv6Rate	Establishment rate of ICMPv6 sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
UDPLiteRate	Establishment rate of UDP-Lite sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
SCTPRate	Establishment rate of SCTP sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
DCCPRate	Establishment rate of DCCP	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
	sessions (per second).			
RawIPRate	Establishment rate of Raw IP sessions (per second).	N/A	Unsigned integer. Value range: 0 to $2^{32} - 1$.	N/A
ReceivedPktsBytes	Number of received packets and packet bytes of different protocols.	Data structure.	Members include: • TCPBytes. • TCPPkts. • UDPBytes. • UDPPkts. • ICMPBytes. • ICMPPkts. • ICMPv6Bytes. • ICMPv6Pkts. • UDPLiteBytes. • UDPLitePkts. • SCTPBytes. • SCTPPkts. • DCCPBytes. • DCCPPkts. • RawIPBytes. • RawIPPkts.	N/A
TCPBytes	Number of received TCP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
TCPPkts	Number of received TCP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
UDPBytes	Number of received UDP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
UDPPkts	Number of received UDP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
ICMPBytes	Number of received ICMP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
ICMPPkts	Number of received ICMP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
ICMPv6Bytes	Number of received ICMPv6 packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
ICMPv6Pkts	Number of	N/A	Unsigned integer.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
	received ICMPv6 packets.		Value range: 0 to $2^{64} - 1$.	
UDPLiteBytes	Number of received UDP-Lite packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
UDPLitePkts	Number of received UDP-Lite packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
SCTPBytes	Number of received SCTP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
SCTPPkts	Number of received SCTP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
DCCPBytes	Number of received DCCP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
DCCPPkts	Number of received DCCP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
RawIPBytes	Number of received Raw IP packet bytes.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A
RawIPPkts	Number of received Raw IP packets.	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	N/A

Session/ConnectionLimit/Ipv4Policies

This table contains IPv4 connection limit policy configurations..

XML structure

```

<Session>
  <ConnectionLimit>
    <Ipv4Policies>
      <Policy>
        <PolicyNumber></PolicyNumber>
      </Policy>
    </Ipv4Policies>
  </ConnectionLimit>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	Ipv4Policies
Table type	Multi-instance table
Row name	Policy
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv4 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/Ipv6Policies

This table contains IPv6 connection limit policy configurations..

XML structure

```
<Session>
  <ConnectionLimit>
    <Ipv6Policies>
      <Policy>
        <PolicyNumber></PolicyNumber>
      </Policy>
    </Ipv6Policies>
  </ConnectionLimit>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv6Policies
Table type	Multi-instance table
Row name	Policy

Restrictions	None
--------------	------

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv6 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/Ipv4LimitRules

This table contains IPv4 connection limit rule configurations.

XML structure

```

<Session>
  <ConnectionLimit>
    <Ipv4LimitRules>
      <Rule>
        <PolicyNumber></PolicyNumber>
        <RuleNumber></RuleNumber>
        <ACLNumber></ACLNumber>
        <ACLName></ACLName>
        <HighThreshold></HighThreshold>
        <LowThreshold></LowThreshold>
        <LimitType>
          <PerSource></PerSource>
          <PerDestination></PerDestination>
          <PerService></PerService>
        </LimitType>
      </Rule>
    </Ipv4LimitRules>
  </ConnectionLimit>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	Ipv4LimitRules

Table type	Multi-instance table
Row name	Rule
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv4 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A
RuleNumber	IPv4 connection limit rule ID.	Index	Unsigned integer. Value range: 1 to 256.	N/A
ACLNumber	IPv4 ACL number	N/A	Unsigned integer. Value range: 2000 to 3999.	Either <i>ACLNumber</i> or <i>ACLName</i> is required, and you cannot configure both.
ACLName	IPv4 ACL name	N/A	String, case-insensitive. Length: 1 to 63 characters.	Either <i>ACLNumber</i> or <i>ACLName</i> is required, and you cannot configure both.
HighThreshold	Upper connection limit	N/A	Unsigned integer. Value range: 1 to 1000000.	When user connections in a range or of a type exceed the upper connection limit, new connections cannot be created. This column is affirmatively chosen item.
LowThreshold	Lower connection limit	N/A	Unsigned integer. Value range: 1 to 1000000.	The lower connection limit cannot be greater than the upper connection limit. New connections cannot be created until the connection number goes below the lower connection limit. This column is affirmatively chosen item.
LimitType	Connection limit type	Data structure.	Members include: • PerSource. • PerDestination. • PerService.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
PerSource	Limits connections by source IP address.	N/A	Boolean: • true—YES • false—NO(default).	N/A
PerDestination	Limits connections by destination IP address.	N/A	Boolean: • true—YES • false—NO(default).	N/A
PerService	Limits connections by service port.	N/A	Boolean: • true—YES • false—NO(default).	N/A

Session/ConnectionLimit/Ipv6LimitRules

This table contains IPv6 connection limit rule configurations.

XML structure

```

<Session>
  <ConnectionLimit>
    <Ipv6LimitRules>
      <Rule>
        <PolicyNumber></PolicyNumber>
        <RuleNumber></RuleNumber>
        <ACLNumber></ACLNumber>
        <ACLName></ACLName>
        <HighThreshold></HighThreshold>
        <LowThreshold></LowThreshold>
        <LimitType>
          <PerSource></PerSource>
          <PerDestination></PerDestination>
          <PerService></PerService>
        </LimitType>
      </Rule>
    </Ipv6LimitRules>
  </ConnectionLimit>
</Session>

```

Table description

Item	Description
Feature name	Session

Table name	Ipv6LimitRules
Table type	Multi-instance table
Row name	Rule
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv6 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A
RuleNumber	IPv6 connection limit rule ID.	Index	Unsigned integer. Value range: 1 to 256.	N/A
ACLNumber	IPv6 ACL number	N/A	Unsigned integer. Value range: 2000 to 3999.	Either <i>ACLNumber</i> or <i>ACLName</i> is required, and you cannot configure both.
ACLName	IPv6 ACL name	N/A	String, case-insensitive. Length: 1 to 63 characters.	Either <i>ACLNumber</i> or <i>ACLName</i> is required, and you cannot configure both.
HighThreshold	Upper connection limit	N/A	Unsigned integer. Value range: 1 to 1000000.	When user connections in a range or of a type exceed the upper connection limit, new connections cannot be created. This column is affirmatively chosen item.
LowThreshold	Lower connection limit	N/A	Unsigned integer. Value range: 1 to 1000000.	The lower connection limit cannot be greater than the upper connection limit. New connections cannot be created until the connection number goes below the lower connection limit. This column is affirmatively chosen item.
LimitType	Connection limit type	Data structure.	Members include: • PerSource. • PerDestination. • PerService.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
PerSource	Limits connections by source IP address.	N/A	Boolean: • true—YES • false—NO(default).	N/A
PerDestination	Limits connections by destination IP address.	N/A	Boolean: • true—YES • false—NO(default).	N/A
PerService	Limits connections by service port.	N/A	Boolean: • true—YES • false—NO(default).	N/A

Session/ConnectionLimit/Ipv4PolicyAppliedGlobally

This table contains IPv4 connection limit policy applied globally.

XML structure

```

<Session>
  <ConnectionLimit>
    <Ipv4PolicyAppliedGlobally>
      <PolicyNumber></PolicyNumber>
    </Ipv4PolicyAppliedGlobally>
  </ConnectionLimit>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	Ipv4PolicyAppliedGlobally
Table type	Single-instance table
Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv4 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/Ipv6PolicyAppliedGlobally

This table contains IPv6 connection limit policy applied globally.

XML structure

```
<Session>
  <ConnectionLimit>
    <Ipv6PolicyAppliedGlobally>
      <PolicyNumber></PolicyNumber>
    </Ipv6PolicyAppliedGlobally>
  </ConnectionLimit>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv6PolicyAppliedGlobally
Table type	Single-instance table
Row name	None
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
PolicyNumber	IPv6 connection limit policy number	Index	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/Ipv4PolicyOnInterfaces

This table contains interfaces to which IPv4 connection limit policy is applied.

XML structure

```
<Session>
  <ConnectionLimit>
    <Ipv4PolicyOnInterfaces>
      <Interface>
        <IfIndex></IfIndex>
        <PolicyNumber></PolicyNumber>
      </Interface>
    </Ipv4PolicyOnInterfaces>
  </ConnectionLimit>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv4PolicyOnInterfaces
Table type	Multi-instance table
Row name	Interface
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
IfIndex	Interface index	Index	Unsigned integer.	This column can only be the index of local VA, global VA or 3 layer interface except loopback, NULL, FC, FCB and encrypt interface.
PolicyNumber	IPv4 connection limit policy number	N/A	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/Ipv6PolicyOnInterfaces

This table contains interfaces to which IPv6 connection limit policy is applied.

XML structure

```
<Session>
  <ConnectionLimit>
    <Ipv6PolicyOnInterfaces>
      <Interface>
        <IfIndex></IfIndex>
        <PolicyNumber></PolicyNumber>
      </Interface>
    </Ipv6PolicyOnInterfaces>
  </ConnectionLimit>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	Ipv6PolicyOnInterfaces
Table type	Multi-instance table
Row name	Interface
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
IfIndex	Interface index	Index	Unsigned integer.	This column can only be the index of local VA, global VA or 3 layer interface except loopback, NULL, FC, FCB and encrypt interface.
PolicyNumber	IPv6 connection limit policy number	N/A	Unsigned integer. Value range: 1 to 32.	N/A

Session/ConnectionLimit/GlobalStatistics

This table contains connection limit global statistics.

XML structure

```
<Session>
  <ConnectionLimit>
    <GlobalStatistics>
      <GlobalStatistic>
        <Chassis></Chassis>
        <Slot></Slot>
        <CPUID></CPUID>
        <Ipv4DroppedPackets></Ipv4DroppedPackets>
        <Ipv6DroppedPackets></Ipv6DroppedPackets>
      </GlobalStatistic>
    </GlobalStatistics>
  </ConnectionLimit>
</Session>
```

Table description

Item	Description
Feature name	Session
Table name	GlobalStatistics
Table type	Multi-instance table
Row name	GlobalStatistic
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
Chassis	ID of the member where the entity resides	Index	Unsigned integer. Value range: 0 to 65534.	N/A
Slot	Slot ID of the entity	Index	Unsigned integer. Value range: 0 to 65534.	N/A
CPUID	CPU ID	Index	Unsigned integer. Value range: 0 to 7.	N/A

Column name	Column description	Column type	Data type and restrictions	Remarks
Ipv4DroppedPackets	Number of dropped IPv4 packets	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	Number of IPv4 packets that are dropped because the upper connection limit is exceeded when an IPv4 connection limit policy is configured globally.
Ipv6DroppedPackets	Number of dropped IPv6 packets	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	Number of IPv6 packets that are dropped because the upper connection limit is exceeded when an IPv6 connection limit policy is configured globally.

Session/ConnectionLimit/InterfaceStatistics

This table contains connection limit statistics on interfaces.

XML structure

```

<Session>
  <ConnectionLimit>
    <InterfaceStatistics>
      <InterfaceStatistic>
        <IfIndex></IfIndex>
        <Chassis></Chassis>
        <Slot></Slot>
        <CPUID></CPUID>
        <Ipv4DroppedPackets></Ipv4DroppedPackets>
        <Ipv6DroppedPackets></Ipv6DroppedPackets>
      </InterfaceStatistic>
    </InterfaceStatistics>
  </ConnectionLimit>
</Session>

```

Table description

Item	Description
Feature name	Session
Table name	InterfaceStatistics
Table type	Multi-instance table

Row name	InterfaceStatistic
Restrictions	None

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
IfIndex	Interface index	Index	Unsigned integer.	This column can only be the index of local VA, global VA or 3 layer interface except loopback, NULL, FC, FCB and encrypt interface.
Slot	Slot ID of the entity	Index	Unsigned integer. Value range: 0 to 65534.	N/A
CPUID	CPU ID	Index	Unsigned integer. Value range: 0 to 7.	N/A
Ipv4DroppedPackets	Number of dropped IPv4 packets	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	Number of IPv4 packets that are dropped because the upper connection limit is exceeded when an IPv4 connection limit policy is configured on an interface.
Ipv6DroppedPackets	Number of dropped IPv6 packets	N/A	Unsigned integer. Value range: 0 to $2^{64} - 1$.	Number of IPv6 packets that are dropped because the upper connection limit is exceeded when an IPv6 connection limit policy is configured on an interface.