

Comware V7 Tracert6 NETCONF XML API Action Reference

Revision Record

Date	Revision Version	Change Description	Author
2014-6-13	V1.00	Initial	dairuiqiang04358

Contents

- Tracert6..... 1
 - Tracert6/IPv6Tracert..... 1
 - XML structure..... 1
 - Responded XML structure 1
 - Table description 1
 - Columns..... 2
 - Responded columns 2

Tracert6

Tracert6/IPv6Tracert

This table is used to test the IPv6 message pass through router from source to destination, and to check the network connection is available.

XML structure

```
<Tracert6>
  <IPv6Tracert>
    <TracertTest>
      <Host></Host>
      <VRF></VRF>
    </TracertTest>
  </IPv6Tracert>
</Tracert6>
```

Responded XML structure

```
<Tracert6>
  <IPv6Tracert>
    <TracertTest>
      <Host></Host>
      <PayloadLength></PayloadLength>
      <Hops></Hops>
      <TracertReply>
        <Sequence></Sequence>
        <PassthroughRouter></PassthroughRouter>
        <ReplyTime></ReplyTime>
      </TracertReply>
      <TestResult></TestResult>
    </TracertTest>
  </IPv6Tracert>
</Tracert6>
```

Table description

Item	Description
Feature name	Tracert6
Table name	IPv6Tracert
Table type	Multi-instance table
Row name	TracertTest

Restrictions	None
--------------	------

Columns

Column name	Column description	Column type	Data type and restrictions	Remarks
Host	IPv6 address or hostname of remote system.	Index	String. Length: 1 to 253 characters.	Example: 1::1 or hostname
VRF	Vrf name.	Index	String. Length: 0 to 31 characters.	An empty string indicates the public network.

Responded columns

Column name	Column description	Column type	Data type and restrictions	Remarks
Host	IPv6 address of remote system.	N/A	String,IPv6 address string.	Example: 1::1.
Hops	The maximum hop limit.	N/A	Unsigned integer. Value range: 1 to 255.	N/A
PayloadLength	The payload length.	N/A	Unsigned integer. Value range: 1 to 4294967295.	N/A
TracertReply	The reply of tracert.	Data structure	Members include: - Sequence. - PassthroughRouter. - ReplyTime.	N/A
Sequence	The Sequence of reply.	N/A	Unsigned integer. Value range: 1 to 4294967295.	N/A
PassthroughRouter	The packet pass through router	N/A	String,IPv6 address string.	Example: 1::1.
ReplyTime	The time of reply.	N/A	Unsigned integer. Value range: 0 to 4294967295. Unit: microsecond.	If value is 4294967295, it means that time out.
TestResult	The test result.	N/A	Boolean: - true—Test success. - false—Test fail.	The timeout to wait for total reply is about 25 seconds.