

SEA-BIRD ELECTRONICS, INC.

1808 136th Place N.E., Bellevue, Washington, 98005 USA
 Phone: (425) 643 - 9866 Fax (425) 643 - 9954 Email: seabird@seabird.com

SENSOR SERIAL NUMBER: 0473
 CALIBRATION DATE: 30-May-07

SBE 37 CONDUCTIVITY CALIBRATION DATA
 PSS 1978: C(35,15,0) = 4.2914 Siemens/meter

COEFFICIENTS:

g = -1.086711e+000	CPcor = -9.5700e-008
h = 1.490543e-001	CTcor = 3.2500e-006
i = -4.107039e-004	WBOTC = -6.9823e-005
j = 5.266538e-005	

BATH TEMP (ITS-90)	BATH SAL (PSU)	BATH COND (Siemens/m)	INST FREQ (Hz)	INST COND (Siemens/m)	RESIDUAL (Siemens/m)
22.0000	0.0000	0.00000	2708.81	0.00000	0.00000
1.0000	34.8962	2.98214	5237.35	2.98215	0.00001
4.5000	34.8755	3.28976	5431.86	3.28975	-0.00001
15.0000	34.8316	4.27329	6011.35	4.27327	-0.00002
18.4999	34.8223	4.61907	6202.11	4.61909	0.00002
24.0000	34.8124	5.17811	6498.48	5.17812	0.00001
29.0000	34.8073	5.70101	6763.75	5.70101	-0.00000
32.5000	34.8048	6.07421	6946.77	6.07421	-0.00000

$$f = \text{INST FREQ} * \sqrt{1.0 + \text{WBOTC} * t} / 1000.0$$

$$\text{Conductivity} = (g + hf^2 + if^3 + jf^4) / (1 + \delta t + \epsilon p) \text{ Siemens/meter}$$

$$t = \text{temperature}[^{\circ}\text{C}]; p = \text{pressure}[\text{decibars}]; \delta = \text{CTcor}; \epsilon = \text{CPcor};$$

$$\text{Residual} = \text{instrument conductivity} - \text{bath conductivity}$$

