



Sea-Bird Scientific
13431 NE 20th Street
Bellevue, WA 98005
USA

+1 425-643-9866
seabird@seabird.com
www.seabird.com

SENSOR SERIAL NUMBER: 0661
CALIBRATION DATE: 01-Dec-20

SBE 37 CONDUCTIVITY CALIBRATION DATA
PSS 1978: C(35,15,0) = 4.2914 Siemens/meter

COEFFICIENTS:

g = -1.043536e+000
h = 1.565272e-001
i = -2.014070e-004
j = 4.357100e-005

CPcor = -9.5700e-008
CTcor = 3.2500e-006
WBOTC = -2.7375e-005

BATH TEMP (° C)	BATH SAL (PSU)	BATH COND (S/m)	INSTRUMENT OUTPUT (Hz)	INSTRUMENT COND (S/m)	RESIDUAL (S/m)
22.0000	0.0000	0.00000	2584.69	0.00000	0.00000
0.9999	34.9663	2.98755	5073.23	2.98755	-0.00000
4.5000	34.9434	3.29553	5262.95	3.29554	0.00001
15.0000	34.8964	4.28040	5827.67	4.28038	-0.00001
18.5000	34.8841	4.62639	6013.26	4.62638	-0.00001
24.0000	34.8705	5.18580	6301.53	5.18582	0.00003
29.0000	34.8583	5.70842	6559.10	5.70841	-0.00001
32.5001	34.8422	6.08001	6736.09	6.07998	-0.00003

$f = \text{Instrument Output(Hz)} * \sqrt{1.0 + \text{WBOTC} * t} / 1000.0$

t = temperature (°C); p = pressure (decibars); $\delta = \text{CTcor}$; $\epsilon = \text{CPcor}$;

Conductivity (S/m) = $(g + h * f^2 + i * f^3 + j * f^4) / (1 + \delta * t + \epsilon * p)$

Residual (Siemens/meter) = instrument conductivity - bath conductivity

