



Sea-Bird Scientific
13431 NE 20th Street
Bellevue, WA 98005
USA

+1 425-643-9866
seabird@seabird.com
www.seabird.com

SENSOR SERIAL NUMBER: 0811
CALIBRATION DATE: 27-Sep-18

SBE 37 CONDUCTIVITY CALIBRATION DATA
PSS 1978: C(35,15,0) = 4.2914 Siemens/meter

COEFFICIENTS:

g = -1.081773e+000
h = 1.506288e-001
i = -4.166794e-004
j = 5.362152e-005

CPcor = -9.5700e-008
CTcor = 3.2500e-006
WBOTC = -7.3368e-005

BATH TEMP (° C)	BATH SAL (PSU)	BATH COND (S/m)	INSTRUMENT OUTPUT (Hz)	INSTRUMENT COND (S/m)	RESIDUAL (S/m)
22.0000	0.0000	0.00000	2688.58	0.00000	0.00000
1.0000	34.8029	2.97493	5202.17	2.97493	0.00000
4.5000	34.7832	3.28191	5395.60	3.28191	-0.00000
15.0000	34.7407	4.26332	5971.78	4.26331	-0.00001
18.5000	34.7315	4.60833	6161.43	4.60835	0.00001
24.0000	34.7218	5.16612	6456.08	5.16612	-0.00000
28.9999	34.7163	5.68777	6719.78	5.68777	-0.00000
32.5000	34.7125	6.05993	6901.65	6.05993	0.00000

$f = \text{Instrument Output(Hz)} * \sqrt{1.0 + \text{WBOTC} * t} / 1000.0$

t = temperature (°C); p = pressure (decibars); $\delta = \text{CTcor}$; $\epsilon = \text{CPcor}$;

Conductivity (S/m) = $(g + h * f^2 + i * f^3 + j * f^4) / (1 + \delta * t + \epsilon * p)$

Residual (Siemens/meter) = instrument conductivity - bath conductivity

