



# SEA-BIRD ELECTRONICS, INC.

13431 NE 20th Street Bellevue, Washington 98005 USA

Phone: (425) 643-9866 Fax: (425) 643-9954 www.seabird.com

## Conductivity Calibration Report

|               |                                          |                 |                |
|---------------|------------------------------------------|-----------------|----------------|
| Customer:     | Monterey Bay Aquarium Research Institute |                 |                |
| Job Number:   | 76732                                    | Date of Report: | 10/30/2013     |
| Model Number: | SBE 37IM                                 | Serial Number:  | 37IM20000-0818 |

*Conductivity sensors are normally calibrated 'as received', without cleaning or adjustments, allowing a determination of sensor drift. If the calibration identifies a problem or indicates cell cleaning is necessary, then a second calibration is performed after work is completed. The 'as received' calibration is not performed if the sensor is damaged or non-functional, or by customer request.*

*An 'as received' calibration certificate is provided, listing the coefficients used to convert sensor frequency to conductivity. Users must choose whether the 'as received' calibration or the previous calibration better represents the sensor condition during deployment. In SEASOFT enter the chosen coefficients. The coefficient 'slope' allows small corrections for drift between calibrations (consult the SEASOFT manual). Calibration coefficients obtained after a repair or cleaning apply only to subsequent data.*

### 'AS RECEIVED CALIBRATION'

☒ Performed ☐ Not Performed

Date: 10/30/2013 Drift since last cal: +0.00010 PSU/month\*

Comments:

### 'CALIBRATION AFTER CLEANING & REPLATINIZING'

☐ Performed ☒ Not Performed

Date: Drift since Last cal: PSU/month\*

Comments:

*\*Measured at 3.0 S/m*

*Cell cleaning and electrode replatinizing tend to 'reset' the conductivity sensor to its original condition. Lack of drift in post-cleaning-calibration indicates geometric stability of the cell and electrical stability of the sensor circuit.*