



Sea-Bird Scientific
13431 NE 20th Street
Bellevue, WA 98005
USA

+1 425-643-9866
seabird@seabird.com
www.seabird.com

SENSOR SERIAL NUMBER: 0825
CALIBRATION DATE: 08-Sep-21

SBE 37 RTC CALIBRATION DATA
ITS-90 TEMPERATURE SCALE

COEFFICIENTS:

rtca0 = 9.999752e-001
rtca1 = 1.675629e-006
rtca2 = -2.609413e-008

BATH TEMPERATURE (° C)	RTC FREQUENCY (Hz)	COMPUTED FREQUENCY (Hz)	RESIDUAL (PPM)
1.0000	0.9999770	0.9999768	-0.2
4.4999	0.9999820	0.9999822	0.2
15.0000	0.9999940	0.9999944	0.4
18.4999	0.9999980	0.9999973	-0.7
23.9999	1.0000000	1.0000004	0.4
29.0000	1.0000020	1.0000018	-0.2
32.5001	1.0000020	1.0000021	0.1

t = temperature (°C)

RTC frequency = $rtca0 + rtca1 * t + rtca2 * t^2$

Residual (PPM) = (Computed RTC frequency - Measured RTC frequency) * 1e6

