

Sea-Bird Electronics, Inc.

13431 NE 20th Street, Bellevue, WA 98005-2010 USA

Phone: (+1) 425-643-9866 Fax (+1) 425-643-9954 Email: seabird@seabird.com

SENSOR SERIAL NUMBER: 0827
CALIBRATION DATE: 18-Apr-12

SBE 37 RTC CALIBRATION DATA
ITS-90 TEMPERATURE SCALE

COEFFICIENTS:

rtca0 = 9.999854e-001

rtca1 = 1.579878e-006

rtca2 = -2.890676e-008

BATH TEMP (ITS-90)	RTC FREQ (Hz)	COMPUTED FREQ (Hz)	RESIDUAL (PPM)
1.0000	0.9999870	0.9999870	-0.0
4.4999	0.9999920	0.9999919	-0.1
14.9999	1.0000020	1.0000026	0.6
18.5000	1.0000050	1.0000047	-0.3
24.0000	1.0000070	1.0000067	-0.3
29.0000	1.0000070	1.0000069	-0.1
32.5000	1.0000060	1.0000062	0.2

$$\text{RTC frequency} = \text{rtca0} + \text{rtca1} * t + \text{rtca2} * t^2$$

$$\text{Residual} = (\text{Computed RTC frequency} - \text{Measured RTC frequency}) * 1e6$$

Date, Delta F ppm

