

SEA-BIRD ELECTRONICS, INC.

1808 136th Place N.E., Bellevue, Washington, 98005 USA

Phone: (425) 643 - 9866 Fax (425) 643 - 9954 Email: seabird@seabird.com

SENSOR SERIAL NUMBER: 1242
CALIBRATION DATE: 15-Nov-06

SBE 37 RTC CALIBRATION DATA
ITS-90 TEMPERATURE SCALE

COEFFICIENTS:

rtca0 = 9.999612e-001

rtca1 = 1.686944e-006

rtca2 = -3.148426e-008

BATH TEMP (ITS-90)	RTC FREQ (Hz)	COMPUTED FREQ (Hz)	RESIDUAL (PPM)
1.0000	0.9999630	0.9999629	-0.1
4.5000	0.9999680	0.9999681	0.1
15.0000	0.9999790	0.9999794	0.4
18.5000	0.9999820	0.9999816	-0.4
23.9999	0.9999840	0.9999835	-0.5
29.0000	0.9999830	0.9999836	0.6
32.5000	0.9999830	0.9999828	-0.2

$$\text{RTC frequency} = \text{rtca0} + \text{rtca1} * t + \text{rtca2} * t^2$$

$$\text{Residual} = (\text{Computed RTC frequency} - \text{Measured RTC frequency}) * 1e6$$

Date, Delta F ppm

