



Sea-Bird Scientific
13431 NE 20th Street
Bellevue, WA 98005
USA

+1 425-643-9866
seabird@seabird.com
www.seabird.com

SENSOR SERIAL NUMBER: 2448
CALIBRATION DATE: 19-Nov-23

SBE 37 CONDUCTIVITY CALIBRATION DATA
PSS 1978: C(35,15,0) = 4.2914 Siemens/meter

COEFFICIENTS:

g = -1.034019e+000
h = 1.479531e-001
i = -4.996366e-004
j = 6.108273e-005

CPcor = -9.5700e-008
CTcor = 3.2500e-006
WBOTC = 7.2604e-006

BATH TEMP (° C)	BATH SAL (PSU)	BATH COND (S/m)	INSTRUMENT OUTPUT (Hz)	INSTRUMENT COND (S/m)	RESIDUAL (S/m)
22.0000	0.0000	0.00000	2651.46	0.00000	0.00000
1.0000	35.0900	2.99712	5236.45	2.99712	-0.00000
4.4999	35.0688	3.30618	5432.88	3.30617	-0.00000
14.9999	35.0245	4.29443	6017.17	4.29441	-0.00002
18.5000	35.0144	4.64180	6209.20	4.64186	0.00006
24.0000	35.0028	5.20329	6507.11	5.20323	-0.00006
29.0000	34.9943	5.72818	6773.44	5.72820	0.00002
32.5000	34.9875	6.10245	6957.14	6.10308	0.00062

$f = \text{Instrument Output(Hz)} * \sqrt{1.0 + \text{WBOTC} * t} / 1000.0$

t = temperature (°C); p = pressure (decibars); $\delta = \text{CTcor}$; $\epsilon = \text{CPcor}$;

Conductivity (S/m) = $(g + h * f^2 + i * f^3 + j * f^4) / (1 + \delta * t + \epsilon * p)$

Residual (Siemens/meter) = instrument conductivity - bath conductivity

