

ECO Calibration and Repairs

Diagnosis: Evaluated instrument (FLNTUSB-287) and found it was out of spec.

Repairs and Modifications: Customer Request NO Shutter. Installed New Face Plate PN: MAA-220524 and ^New 9V Batteries PN: EXA-ZX0064

ECO Standard Service:

The instrument bulkhead connector, pressure housing and window\optics are inspected for damage. Instrument is checked to determine proper functionality. Incoming settings and memory are collected if incoming condition allows.

If applicable, a pre-service characterization is performed. Data is analyzed and Instrument is rescaled.

The head is inspected for cracks in detector and motor bores. Case seals, shaft, shaft seal, faceplate, wiper, desiccant pack, and batteries (if equipped) are replaced. Noise, stability, and live pressure test performed.

Final calibration and characterization is completed. Including calibration of thermistor and pressure sensor (if equipped). A device file, repair sheet, and new characterization sheets are provided to customer via USB.