


CP1 104479-7
CP2 104479-7
CP3 104479-7
CP4 104479-7
CP5 104479-7


J1
103648-5



1 VCC (BROWN)
2 CLK (RED)
3 DATA (ORANGE)
4 GND (YELLOW)
5 INDEX (GREEN)
6

APPLY TWO WIRE HARNESS LABELS
IN THESE LOCATIONS

J2
50-57-9405



CP6 16-02-0103
CP7 16-02-0103
CP8 16-02-0103
CP9 16-02-0103
CP10 16-02-0103

LOCATION	WIRE HARNESS LABEL	"L"	TOLERANCE
PROCESSING	WH40	34"	-0.20"/+0.50"
PROCESSING	WH42	34"	-0.20"/+0.50"
COLLECTION	WH17	28"	-0.20"/+0.50"
COLLECTION	WH19	28"	-0.20"/+0.50"
PROCESSING	WH44	27"	-0.20"/+0.50"
COLLECTION	WH21	14"	-0.20"/+0.50"
ISAMPLER	WH11	20"	-0.20"/+0.50"
PROCESSING	WH101	36"	-0.20"/+0.50"

*TWIST 1 & 4 TOGETHER
*TWIST 2, 3, & 5 TOGETHER
*22AWG MIL SPEC TYPE "E" WIRE

MONTEREY BAY AQUARIUM RESEARCH INSTITUTE
7700 SANDHOLDT ROAD
MOSS LANDING, CA 95039
(831) 775-1700 www.mbari.org
Copyright MBARI 2000



Title Absolute Encoder Harness			Number _	
Size A	Engineer Scott Jensen	Layout _	Filename ESP_System	Rev 0.0.0
	Date: Wednesday, June 04, 2008	Sheet 1 of 1		