

CP7
CP8
CP9
CP10
CP11
CP12

16-02-0103
16-02-0103
16-02-0103
16-02-0103
16-02-0103
16-02-0103

To LatchHome Board


J2
50-57-9406



1 Home+5 (BROWN)
2 HomeSignal (RED)
3 SignalGND (ORANGE)
4 Latch+3.3 (YELLOW)
5 LatchInput (GREEN)
6 CoreOutput (BLUE)

To Core Board

J1




103648-5

CP2
CP3
CP4
CP1
CP5
CP6

104479-7
104479-7
104479-7
104479-7
104479-7
104479-7

↑ APPLY TWO WIRE HARNESS LABELS IN THESE LOCATIONS ↑



LOCATION	WIRE HARNESS LABEL	"L"	TOLERANCE
MANIPULATOR	WH68	6.5"	-0.20"/+0.50"
STORAGE	WH79	6"	-0.20"/+0.50"

*TWIST ALL WIRES TOGETHER
*22AWG MIL SPEC TYPE "E" WIRE

MONTEREY BAY AQUARIUM RESEARCH INSTITUTE
7700 SANDHOLDT ROAD
MOSS LANDING, CA 95039
(831) 775-1700 www.mbari.org
Copyright MBARI 2000



Title Latch Home Harness			Number _	
Size A	Engineer Scott Jensen	Layout _	Filename ESP_System	Rev 0.0.0
Date: Wednesday, June 04, 2008		Sheet 1	of 6	