

MATERIAL SAFETY DATA SHEET

MS206

Power-Cut™ 390

Page 1 of 3

PRODUCT NAME: **Power-Cut™ 390**
PRODUCT CLASS: WATER SOLUBLE OIL CUTTING FLUID

=== **SECTION I MANUFACTURER IDENTIFICATION** =====

MANUFACTURER'S NAME: DoALL COMPANY
ADDRESS: 254 No. Laurel Ave. Des Plaines, IL 60016.
EMERGENCY PHONE: (800) 535-5053 (INFOTRAC)
INFORMATION: (847) 803-7262
REVISION DATE: April 26, 2001

=== **SECTION II HAZARDOUS INGREDIENTS IDENTIFICATION** =====

OCCUPATIONAL EXPOSURE LIMITS

<u>INGREDIENTS:</u>	<u>CAS #:</u>	<u>OSHA PEL:</u>	<u>ACGIH TLV:</u>	<u>PERCENT:</u>
Severely Hydro-treated Naphthenic Oil	64742-52-5	5mg./cu. m.	5mg./cu. m.	40.0-50.0
Hydrotreated middle Petroleum distillate	64742-46-7	5 mg./cu. m.		5.0-15.0
Triethanolamine	102-71-6	5 mg./cu. m.		3.0-5.0
2-Butoxy ethanol	111-76-2	240 ppm	121 ppm	3.0-5.0

=== **SECTION III PHYSICAL DATA** =====

Boiling Point: >212 °F
Specific Gravity: 0.94 (Water = 1)
Vapor Pressure: ND
Melting Point: NA
Vapor Density: ND
Evaporation Rate: ND (BuAc = 1)
Solubility in Water: Emulsifies
pH: 9.5 (@ 5%)
Appearance: Dark-brown Liquid
Odor: Oily aroma

=====
=== **SECTION IV FIRE AND EXPLOSION DATA** =====

FLASH POINT: 350 °F COC.
EXTINGUISHING MEDIA: Carbon Dioxide, Foam, or Dry Chemical.
FIRE FIGHTING PROCEDURES: Water stream or spray, to cool containers to prevent vapor formation and ignition, may spread fire. Fog nozzles are preferred if water is used. Wear SCBA gear in fire area.
UNUSUAL FIRE AND
EXPLOSION HAZARDS: None.

=====
=== **SECTION V HEALTH HAZARD DATA** =====

ROUTES OF EXPOSURE AND EFFECTS OF OVER-EXPOSURE:

INHALATION: Breathing difficulty.
EYE CONTACT: Minor irritation.
SKIN CONTACT: Defatting, and/or minor irritation.
SKIN ABSORPTION: Not expected to occur.
INGESTION: Nausea, and/or diarrhea.

CARCINOGENICITY:

LISTED BY NTP: No
LISTED BY IARC: No
LISTED BY OSHA: No

EMERGENCY FIRST AID PROCEDURES:

INHALATION: Remove person to fresh air. If necessary, support breathing. Get Medical attention.
EYE CONTACT: Flush with water for 15 minutes. If irritation persists, get Medical attention.
SKIN CONTACT: Wash exposed area with mild soap and warm water only. Do not use harsh soap or solvent.
SKIN ABSORPTION: Get Medical attention.
INGESTION: Keep person warm and quiet. Get Medical attention. Do not induce vomiting.

=====
=== **SECTION VI REACTIVITY DATA** =====

STABILITY: Stable.
INCOMPATIBILITY: Strong oxidizers.
HAZARDOUS DECOMPOSITION PRODUCTS: Oxides of carbon, sulfur and nitrogen compounds, and hydrogen chloride.
HAZARDOUS POLYMERIZATION: Will not occur.

=====
=== **SECTION VII HANDLING PRECAUTIONS** =====

IN CASE OF ACCIDENTAL RELEASE:

SMALL SPILLS: Use absorbent material.
LARGE SPILLS: Dike and pump into drums.
RESIDUE: Mop with soap and water.
WASTE DISPOSAL METHOD: Treat as an oily waste and dispose of in accordance with all local, state, and federal regulations.
STORAGE: Store dry in a closed container in a cool place away from any fire source.
OTHER PRECAUTIONS: Avoid breathing MIST.

=====
=== **SECTION VIII PROTECTIVE MEASURES** =====

VENTILATION: General mechanical ventilation should be adequate. If misting occurs, provide local ventilation.

GLOVES: The use of NEOPRENE gloves that are impermeable to oil is recommended.

EYE PROTECTION: Safety goggles with side shields or face shield are recommended.

OTHER PROTECTION: An emergency shower and eyewash should be available in the work area. Practice reasonable personal hygiene. Wash exposed skin with mild soap and warm water only. Oil-soaked clothing should be changed promptly and laundered before re-wearing.

=====
=== **SECTION IX REGULATION COMPLIANCE INFORMATION** =====

CAA: Contains no ozone depleting substance.

DOT: Not classified as hazardous.

RCRA: As received, not a hazardous waste material.

SARA: Contains 3% 2-Butoxy Ethanol (111-76-2).

TSCA: All ingredients are registered.

VOC: Volatile organic carbon content is 38 g./L.

=====
=== **SECTION X HMIS** =====

HEALTH: 2

FLAMMABILITY: 1

REACTIVITY: 0

=====

=====

Abbreviations and Symbols used in this MSDS:

NA Not Applicable < - Less Than

ND Not Determined > - Greater Than

BuAc Butyl Acetate

=====

Data in this MSDS is believed to be correct and reliable. However, The DoALL Co. does not assume responsibility for it, or any recommendations contained in it, inasmuch as conditions and methods of use are beyond our control. Further, we make no warranty, expressed or implied, of any kind regarding this product or its use, and purchaser assumes all risks of use or handling either in accordance with directions or not.

=====