


► General data



Header, nominal current: 20 A, rated voltage: 400 V, pitch: 7.62 mm, no. of positions: 4, mounting: Soldering

Order number	1804810
Type	PC 4/ 4-G-7,62

Barcode number	4017918046255
Unit pack	50 Piece
Customs tariff	85369010000

► Technical data

Dimensions / positions

Pitch	7.62 mm
Dimension a	22.86 mm
Number of positions	4
Pin dimensions	1 x 0,8 mm
Hole diameter	1.3 mm

Technical data

Insulating material group	IIIa
Rated surge voltage (III/3)	6 kV
Rated surge voltage (III/2)	6 kV
Rated surge voltage (II/2)	6 kV
Rated voltage (III/2)	630 V
Rated voltage (II/2)	630 V
Connection in acc. with standard	EN-VDE
Nominal current I_N	20 A
Nominal voltage U_N	400 V
Maximum load current	20 A
Insulating material	PBT
Inflammability class acc. to UL 94	V0

► Certificates

UL


Nominal voltage U_N	300 V
Nominal current I_N	20 A

CSA


Nominal voltage U_N	300 V
Nominal current I_N	20 A

▸ Drawings

Drilling diagram



Dimensioned drawing



Approval logo



► Accessories

Item	Designation	Description
Assembly		
1827570	BF-PC 4	Mounting flange, is snapped onto the left and right of the headers, for screw connection with PC 4/...-STF-7.62
Marking		
0804549	SK 7,62/3,8:FORTL.ZAHLEN	Marker card, printed horizontally, self-adhesive, 12 identical decades marked 1-10, 11-20 etc. up to 91-100, sufficient for 120 terminal blocks
Plug/Adapter		
1600027	CP-HCC 4	Coding section, is inserted into the slot on the plug and panel mounting base, red insulating material

► Additional products

General

1848915	PC 4 HV/ 4-ST-7,62
1882395	PC 4 HV/ 4-STF-7,62
1804920	PC 4/ 4-ST-7,62
1828265	PC 4/ 4-STF-7,62
1840175	PCC 4/ 4-ST-7,62

► Address

Phoenix Contact GmbH & Co. KG
Flachsmarktstr. 8
32825 Blomberg
Germany
Tel + 49 - (0) 52 35 - 3-00
Fax + 49 - (0) 52 35 - 3-4 12 00
www.phoenixcontact.com

© Phoenix Contact
Technical modifications reserved