

4

3

2

1

22AWG 19 Strand Teflon Jacket
BS3G210 Type A Wire
1.1mm MAX Insulation Diameter.
Color: Yellow
(2x)

22AWG Stranded Drain Wire
(3x)

Braided Shield

3X
24AWG 19 Strand Teflon Jacket
BS3G210 Type A Wire
0.95mm MAX Insulation Diameter.
Color: Blue, Gray, and Violet

22AWG 19 Strand Teflon Jacket
BS3G210 Type A Wire
1.1mm MAX Insulation Diameter.
Color: Red

24AWG Stranded Drain Wire

PVC or Silicone Jacket

Foil Shield
(3x)

Thin PVC Jacket

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS
DRAWING IS THE SOLE PROPERTY OF
<INSERT COMPANY NAME HERE>. ANY
REPRODUCTION IN PART OR AS A WHOLE
WITHOUT THE WRITTEN PERMISSION OF
<INSERT COMPANY NAME HERE> IS
PROHIBITED.

		UNLESS OTHERWISE SPECIFIED:		NAME	DATE	TITLE: ESP Custom Cable		
		DIMENSIONS ARE IN INCHES TOLERANCES: FRACTIONAL ± ANGULAR: MACH ± BEND ± TWO PLACE DECIMAL ± THREE PLACE DECIMAL ±	DRAWN	J.Rosal				
			CHECKED					
			ENG APPR.					
			MFG APPR.					
		INTERPRET GEOMETRIC TOLERANCING PER:	Q.A.			SIZE DWG. NO. REV B XXXXXXXXX		
		MATERIAL	COMMENTS:					
NEXT ASSY	USED ON	FINISH						
APPLICATION		DO NOT SCALE DRAWING				SCALE: 1:1	WEIGHT:	SHEET 1 OF 1

4

3

2

1

B

B

A

A