

Company: _____

Contact: _____


Project Name: _____

Phone: _____

RoHS compliant? _____

Notes: _____

NPT Fitting with Tube



Ask us about
RoHS compliant parts.

SELECT YOUR RESISTANCE

RES. @ 25°C (OHMS)	PART #	R-T CURVE	ALPHA (?)
1,000	QTMC-2	Z	(-4.4%/°C)
2,252	QTMC-7	Z	(-4.4%/°C)
3,000	QTMC-9	Z	(-4.4%/°C)
5,000	QTMC-11	Z	(-4.4%/°C)
10,000	QTMC-14	Z	(-4.4%/°C)
20,000	QTMC-19	Z	(-4.4%/°C)
100,000	QTMC-43	V	(-4.9%/°C)
10,000	QTMC-82	S	(-4.0%/°C)
30,000	QTMC-89	M	(-4.2%/°C)

SELECT YOUR TOLERANCE

POINT MATCHED THERMISTOR
K = 10%
J = 5%
G = 2%
F = 1%
INTERCHANGEABLE THERMISTOR
D3 = +/- .1°C (0°C-70°C)
C3 = +/- .2°C (0°C-70°C)
B3 = +/- .5°C (0°C-70°C)
A3 = +/- 1°C (0°C-70°C)

SELECT YOUR WIRE

GAUGE	INSULATION	RATING
A #28 AWG	KYNAR	UL1422
B #26 AWG	KYNAR	UL1422
C #24 AWG	TEFLON	UL1213
D #24 AWG	PVC	TYPE B
E #22 AWG	PVC	UL1061
F #22 AWG	TEFLON	UL1180
G #24 AWG	TEFLON	UL TYPE CMP
H #22 AWG	PVC	UL TYPE CM

CONTACT QTI FOR TEMPERATURE RANGES

SELECT YOUR CONNECTOR

MFG.	TERMINALS	WIRE
1 MOLEX	43030-007	#20 - #24 AWG
2 AMP	634816-2	#28 AWG
3 PANDUIT	DVF18-250	#22 - #26 AWG
4 PANDUIT	DV18-250	#22 - #26 AWG

QT06001B
Stainless Steel Housing
Wire Options A,B



Quality Thermistor, Inc.

(800) 554-4784
(208) 376-4754 FAX
www.thermistor.com
sales@thermistor.com

THIS DRAWING AND THE INFORMATION IS THE PROPERTY OF QUALITY THERMISTOR AND ALL UNAUTHORIZED USE AND REPRODUCTION IS PROHIBITED.