

ABS-M30

Production-Grade Thermoplastic for
Fortus 3D Production Systems



ABS-M30 is up to 25-70 percent stronger than standard Stratasys ABS and is an ideal material for conceptual modeling, functional prototyping, manufacturing tools, and end-use-parts. ABS-M30 has greater tensile, impact, and flexural strength than standard ABS. Layer bonding is significantly stronger than that of standard ABS, for a more durable part. This results in more realistic functional tests and higher quality parts for end use. When combined with a Fortus® 3D Production System, ABS-M30 gives you Real Parts™ that are stronger, smoother, and with better feature detail.

Mechanical Properties ¹	Test Method	English	Metric
Tensile Strength (Type 1, 0.125", 0.2"/min)	ASTM D638	5,200 psi	36 MPa
Tensile Modulus (Type 1, 0.125", 0.2"/min)	ASTM D638	350,000 psi	2,400 MPa
Tensile Elongation (Type 1, 0.125", 0.2"/min)	ASTM D638	4%	4%
Flexural Strength (Method 1, 0.05"/min)	ASTM D790	8,800 psi	61 MPa
Flexural Modulus (Method 1, 0.05"/min)	ASTM D790	336,000 psi	2,300 MPa
IZOD Impact, notched (Method A, 23°C)	ASTM D256	2.6 ft-lb/in	139 J/m
IZOD Impact, un-notched (Method A, 23°C)	ASTM D256	5.3 ft-lb/in	283 J/m

Thermal Properties ²	Test Method	English	Metric
Heat Deflection (HDT) @ 66 psi, 0.125" unannealed	ASTM D648	204°F	96°C
Heat Deflection (HDT) @ 264 psi, 0.125" unannealed	ASTM D648	180°F	82°C
Vicat Softening Temperature (Rate B/50)	ASTM D1525	210°F	99°C
Glass Transition (Tg)	DSC (SSYS)	226°F	108°C
Coefficient of Thermal Expansion (flow)	ASTM E831	4.9E-05 in/in/°F	8.82E-05 mm/mm/°C
Coefficient of Thermal Expansion (xflow)	ASTM E831	4.7E-05 in/in/°F	8.46E-05 mm/mm/°C
Melt Point	-----	Not Applicable ³	Not Applicable ³

Electrical Properties ⁴	Test Method	Value Range
Volume Resistivity	ASTM D257	4.0x10e14 - 5.0x10e13 ohms
Dielectric Constant	ASTM D150-98	2.9 - 2.7
Dissipation Factor	ASTM D150-98	.0052 - .0049
Dielectric Strength	ASTM D149-09, Method A	370 - 71 V/mil



Stratasys®

Production
Series

ABS-M30



Other ²	Test Method	Value
Specific Gravity	ASTM D792	1.04
Flame Classification	UL94	HB (0.09", 2.50 mm)
Rockwell Hardness	ASTM D785	109.5
UL File Number	-----	E345258

System Availability	Layer Thickness Capability	Support Structure	Available Colors
Fortus 360mc	0.013 inch (0.330 mm)	Soluble Supports	■ Ivory
Fortus 400mc	0.010 inch (0.254 mm)		□ White
Fortus 900mc	0.007 inch (0.178 mm)		■ Black
	0.005 inch (0.127 mm) ⁵		■ Dark Grey
			■ Red
			■ Blue

The information presented are typical values intended for reference and comparison purposes only. They should not be used for design specifications or quality control purposes. End-use material performance can be impacted (+/-) by, but not limited to, part design, end-use conditions, test conditions, etc. Actual values will vary with build conditions. Tested parts were built on Fortus 400mc @ 0.010" (0.254 mm) slice. Product specifications are subject to change without notice.

The performance characteristics of these materials may vary according to application, operating conditions, or end use. Each user is responsible for determining that the Stratasys material is safe, lawful, and technically suitable for the intended application, as well as for identifying the proper disposal (or recycling) method consistent with applicable environmental laws and regulations. Stratasys makes no warranties of any kind, express or implied, including, but not limited to, the warranties of merchantability, fitness for a particular use, or warranty against patent infringement.

¹Build orientation is on side long edge.

²Literature value unless otherwise noted.

³Due to amorphous nature, material does not display a melting point.

⁴All Electrical Property values were generated from the average of test plaques built with default part density (solid). Test plaques were 4.0 x 4.0 x 0.1 inches (102 x 102 x 2.5 mm) and were built both in the flat and vertical orientation. The range of values is mostly the result of the difference in properties of test plaques built in the flat vs. vertical orientation.

⁵0.005 inch (0.127 mm) layer thickness not available for Fortus 900mc.

Stratasys | www.stratasys.com | info@stratasys.com

7665 Commerce Way
Eden Prairie, MN 55344
+1 888 480-3548 (US Toll Free)
+1 952 937-3000 (Intl)
+1 952 937-0070 (Fax)

2 Holtzman St.,
Science Park, PO Box 2496
Rehovot 76124, Israel
+972 74 745-4000
+972 74 745-5000 (Fax)

Local Street Address
City, State, Zip
Phone #
Fax #

©2013 Stratasys Inc. All rights reserved. Stratasys, FDM, Fortus and Finishing Touch are registered trademarks of Stratasys Inc. FDM Technology, Fused Deposition Modeling, Fortus 200mc, Fortus 250mc, Fortus 360mc, Fortus 400mc, Fortus 900mc, Insight, Control Center, FDM Team, Smart Supports, SR-30, SR-100, ABSplus, ABS-ESD7, and TouchWorks are trademarks of Stratasys, Inc. "ULTEM is a trademark of SABIC Innovative Plastics IP BV. All other trademarks are the property of their respective owners, and Stratasys assumes no responsibility with regard to the selection, performance, or use of these non-Stratasys products. Product specifications subject to change without notice. Printed in the USA. FortusABSM30MaterialSpecSheet-US-1013

At the core:

Advanced FDM Technology™

Fortus systems are based on patented Stratasys FDM (Fused Deposition Modeling) technology. FDM is the industry's leading additive manufacturing technology, and the only one that uses production grade thermoplastics, enabling the most durable parts.

Fortus systems use a wide range of thermoplastics with advanced mechanical properties so your parts can endure high heat, caustic chemicals, sterilization, and high impact applications.

No special facilities needed

You can install a Fortus 3D Production System just about anywhere. No special venting is required because Fortus systems don't produce noxious fumes, chemicals, or waste.

No special skills needed

Fortus 3D Production Systems are easy to operate and maintain compared to other additive fabrication systems because there are no messy powders or resins to handle and contain. They're so simple, an operator can be trained to operate a Fortus system in less than 30 minutes.

Get your benchmark on the future of manufacturing

Fine details. Smooth surface finishes. Accuracy. Strength. The best way to see the advantages of a Fortus 3D Production System is to have your own part built on a Fortus system. Get your free part at: stratasys.com.